

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23581-00-01
Spot: S2S2NE Sec/Twnshp/Rge: 29-30S-7E
2939 feet from S Section Line, 1576 feet from E Section Line
Lease Name: STOLP Well #: 16
County: COWLEY Total Vertical Depth: 2940 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2940		50 SX CMT
SURF	8.625	335		225 SX CMT

A 9555

Well Type: EOR UIC Docket No: E17807.2 Date/Time to Plug: 11/07/2005 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: BRENT WHITEMAN Company: GEN-DOR OIL COMPANY Phone: (620) 467-2615

Proposed Plugging Method: FILL UP BOTTOM OF WELL GRAVEL TO 50' ABOVE THE PERFS THEN DUMP BAIL 6 SX CMT ON TOP OF GRAVEL. SHOOT OF CSG AND PULL CSG OUT OF THE WELL CIRCULATE CMT FROM DEPTH OF 385' (OR AS KCC REQUIRES) TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/08/2005 12:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

9/11/2005 -- Sanded back 50' above perforations at 2839'. Dumped bail 6 sacks of cement on top.
11/5/2005 -- Shot 4-1/2" casing at 1482' and laid casing down.
11/7/2005 -- RIH with tubing at 385' and pumped 138 sacks of 60/40 posmix with 4% gel to surface.
11/8/2005 -- Tagged cement at 198'. RIH with tubing at 195' and pumped 70 sacks of 60/40 posmix with 4% gel to surface.
Gen-Dor #673551

Perfs:

Top	Bot	Thru	Comments
2891	2900		
0			

RECEIVED
KCC DISTRICT #2
NOV 22 2005
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 2005

Remarks:

Plugged through: TBG

District: 02

Signed Duane R. Krueger
(TECHNICIAN)

INVOICED

DATE 12-8-05
INV. NO. 2006060826

2