

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21406-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 16-34S-19W
1120 feet from N Section Line, 1450 feet from W Section Line
Lease Name: RANSOM Well #: 16-1
County: COMANCHE Total Vertical Depth: 6290 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5225		WITH 4 SX CMT
PROD	4.5	5420	4424	WITH 175 SX CMT
SURF	8.625	644		WITH 325 SX CMT

#20443

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2005 10:30 AM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC
Proposal Rcvd. from: DON SANDERS Company: DAYSTAR PETROLEUM Phone: (316) 755-3523

Proposed Plugging Method: CIBP & 4 SX CMT. PLUG AT 1000' WITH 40 SX CMT. PLUG AT 650' WITH 80 SX CMT. PLUG AT 40' WITH 10 SX CMT. USE 12 SX GEL FOR SPACER.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2005 3:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5225' WITH 4 SX CMT. 1ST PLUG AT 1000' WITH 12 SX GEL & 40 SX CMT. 2ND PLUG PULL CASING TO 654' & PUMP 80 SX CMT. 3RD PLUG PULL CASING TO 40' & PUMP 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5275	5290		

RECEIVED
DEC 02 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Jerry W. Stapleton PART II
(TECHNICIAN)

INVOICED
DATE 12-8-05
INV. NO. 2006060827

FORM CR-278