

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Chesapeake Operating, Inc.
Address: P. O. Box 18496, Oklahoma City, OK 73154-0496
Phone: (405) 848-8000 Operator License #: 32334
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 01/11/05 (Date)
by: David Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 5456 Bottom: 5463 T.D. 5960

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-189-22350-00-00
Lease Name: MLP Crawford A
Well Number: 1-34
Spot Location (QQQQ): _____ - SE - SE - NW
1027 Feet from North / South Section Line
2307 Feet from East / West Section Line
Sec. 34 Twp. 31 S. R. 39 East West
County: STEVENS
Date Well Completed: 11/13/2000
Plugging Commenced: 11/11/05
Plugging Completed: 11/11/05

KCC
BEM
12-8-05
RBDMS
CP 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1808	
				4-1/2	5960	

RECEIVED
DEC 08 2005
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU Allied Services, pump 300# CS hulls, pump 100# hulls w/25 sx 60/40 w/6% gel, pump 50 bbls mud spacer, pump 100 sx 60/40 w/6% gel, load, pressure to 350#, load surf. csg. w/15 sx, pressure to 200#, RDMO, Cut casing, weld ID plate, Back fill pit - P&A complete

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: _____
Address: P. O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Chesapeake Operating, Inc.
State of OK County, OK, ss.

Barbara J. Bale (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC
LUCRETIA A. MORRIS
Notary Public
State of Oklahoma
Commission # 00018352 Expires 11/27/08

(Signature) Barbara J. Bale
(Address) P. O. Box 18496, Oklahoma City, OK 73154-0496

and SWORN TO before me this 7th day of December, 2005

Lucretia A. Morris My Commission Expires: 11/27/08
Notary Public

Bur

ALLIED CEMENTING CO., INC. 19954

Federal Tax I.D.# ~~00-0000000~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: OK/07

DATE <u>11/10/05</u>	SEC. <u>34</u>	TWP. <u>31S</u>	RANGE <u>39W</u>	CALLED OUT	ON LOCATION <u>10:00 AM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>11:30 AM</u>
LEASE <u>MLP Crawford</u>		WELL # <u>1-34</u>		LOCATION <u>Moscow 1/2 SW 19 1/2 W 1 S 2 E S 1 S</u>		COUNTY <u>STEVENS</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR _____ OWNER Sam C

TYPE OF JOB O.H.P

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 11.6" DEPTH 5960

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 350 MINIMUM 50

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. 5456, 5467

DISPLACEMENT _____

CEMENT

AMOUNT ORDERED 400 # C.S. 17ulls

175 sks 60/40 + 67 gal

used 140 sks 60/40 + 67 gal

COMMON	<u>84 sks</u>	@	<u>12.00</u>	<u>840.00</u>
POZMIX	<u>56 sks</u>	@	<u>4.70</u>	<u>263.20</u>
GEL	<u>7 sks</u>	@	<u>14.00</u>	<u>98.00</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>4 sks</u>	@	<u>21.00</u>	<u>84.00</u>

EQUIPMENT

PUMP TRUCK # 191 CEMENTER Max

HELPER Wayne

BULK TRUCK # 377 DRIVER Jarrod

BULK TRUCK # _____ DRIVER _____

RECEIVED

DEC 08 2005

KCC WICHITA

HANDLING	<u>184.188</u>	@	<u>1.60</u>	<u>294.70</u>
MILEAGE	<u>60/50/mi</u>		<u>56/10</u>	<u>552.00</u>
TOTAL				<u>2047.60</u>
				<u>2150.00</u>

REMARKS:

Hook up to 4 1/2 Csg Pump 400 # C.S. Hulls
Mix 25 sks Cmt Pump 50 PBL Mud
Mix 100 sks Cmt Pressure Csg to 350 PSI
Hook up to Ann Mix 15 sks Cmt
Pressure Ann to 300 PSI

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 750.00

EXTRA FOOTAGE @ _____

MILEAGE 50 MI @ 5.00 250.00

MANIFOLD @ _____

@ _____

@ _____

CHARGE TO: Chesapeake Operating

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL 1000.00

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE AK Grayson

WR Grayson
PRINTED NAME