

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
DEC 02 2005
KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757, Wichita, KS 67201-2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7-5-05 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3552' Bottom: 3634' T.D. 3787'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-065-21,682-00-00
Lease Name: Cooley
Well Number: #1
Spot Location (QQQQ): NE - SW - SE - _____
990 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 17 Twp. 9 S. R. 21 East West
County: Graham
Date Well Completed: 10-9-82
Plugging Commenced: 7-18-05
Plugging Completed: 7-18-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil, Water	0'	245'	8 5/8"	245'	0'
Production	Oil, Water	0'	3784'	5 1/2"	3784'	0'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hook up to 8 5/8" and pressure to 300#. Had cement inside 8 5/8" when bull plug removed. Hook up to 5 1/2" and pump 200 sx SMD w/600# hulls max pressure 300#. Let cement sit for 1 hr. Top off 5 1/2" w/40 sx cement, Let cement sit for 1 hr. Top off 5 1/2" w/10 sx. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: P.O. Box 466, Ness City, KS 67560-0466

Name of Party Responsible for Plugging Fees: Gore Oil Company
State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Larry M Jack
(Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED and SWORN TO before me this 30th day of November, 20 05
Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Burr