

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Horseshoe Operating, Inc.
Address: 110 W. Louisiana, Suite 200 Midland, Texas 79701
Phone: (432) 683-1448 Operator License #: 4894
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/7/05 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

API Number: 15 - 071-20023-00-00
Lease Name: Miller
Well Number: 1-A
Spot Location (QQQQ): C - SW - _____ - _____
1320 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 23 Twp. 20S S. R. 40 East West
County: Greeley
Date Well Completed: 7/3/73
Plugging Commenced: 11/29/05
Plugging Completed: 11/29/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Surf</u>				<u>8-5/8</u>	<u>7jts-296</u>	
<u>Prod</u>				<u>4-1/2</u>	<u>73jts-2843</u>	

KCC
BEM
12-9-05
RBDms
CP 2/3

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


RU Peak Wireline tag top of packer @ 1531'. Set bridge plug @ 1350'. Dump 2 sxs cement on top of plug. Perforate 4-1/2 casing @ 1320 with 4 holes. RU Allied Cementing. Pump into perfs @ 500#. Pump 80 sxs 60/40 poz 6% gel dwn 4-1/2 casing. Then follow w/20 sxs and 200# hulls, then 90 sxs. Pressured 1000#, holding @ 750#. RU on annulus and pump 210 sxs 60/40 poz 6% gel Pressure up to 150#, holding 50#.

Name of Plugging Contractor: Allied Cementing License #: 99994
Address: Russell, KS
Name of Party Responsible for Plugging Fees: Horseshoe Operating, Inc.
State of Texas County, Midland, ss.

RECEIVED
DEC 05 2005
KCC WICHITA

Debbie Franklin (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Debbie Franklin
(Address) 110 W. Louisiana, Ste. 200 Midland, Texas



SUBSCRIBED and SWORN TO before me this 1 day of December, 20 05
Nancy J. Christmas My Commission Expires: 10/26/08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bum