

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606
Type of Well: Oil Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/16/05 (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
3564-3569 Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 147-20555-00-00
Lease Name: Johnson B
Well Number: #19
Spot Location (QQQQ): SE - NE - SE -
1700 Feet from North / South Section Line
300 Feet from East / West Section Line
Sec. 31 Twp. 5 S. R. 20 East West
County: Phillips
Date Well Completed: 10/93
Plugging Commenced: 11/16/05
Plugging Completed: 11/16/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	335	8 5/8	335	0
	Production	Surface	3638	5 1/2	3638	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 3585' & tagged fill. Pulled to 3560'. Hooked Swift Services to tbg & pumped 80 sx SMD w/400# hulls. Pulled pipe to 1850' & pumped 95 sx w/300# hulls. Pulled tbg out of hole. Hooked to surface pipe & pumped 10 sx to 100#. Hooked to 5 1/2" & pumped 10 sx to 500#. SI well. Approved by Rich Williams w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202
Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.

RECEIVED
DEC 06 2005
KCC WICHITA

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]
(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 5th day of December, 20 05
Susan Brady My Commission Expires: 11-4-07
Notary Public

[Handwritten mark]