

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD DEC 05 2005 K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

Lease Operator: JTC Oil, Inc.

Address: P.O. Box 910 Louisburg, KS 66053

Phone: (913) 837-3411 Operator License #: 32834

Type of Well: ENHR Docket #: E18352 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Squirrel Depth to Top: 730 Bottom: 749 T.D. 770

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-059-19304-00-01

Lease Name: Moldenhauer

Well Number: W2

Spot Location (QQQQ): N2 NE NW1/4 - 4950 Feet from North / South Section Line

3300 Feet from East / West Section Line

Sec. 32 Twp. 15 S. R. 21 East West

County: Franklin

Date Well Completed: 1977

Plugging Commenced: 8-17-2004

Plugging Completed: 8-17-2004

KCC BEM 12-9-05 Per Operator Tom Cain

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for Squirrel oil formation and casing sizes.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Established circulation down 1" inside of 2" and open hole. Mixed and pumped 45 sx 50/50 pos, 5# gilsonite, 5% salt, 2% gel, 1/4# flo-seal. Circulated cement to surface. Pulled 1" out and topped off with 5 sx cement. Hooked to 2" and injected 10 sx cement into casing. Well held 1250 PSI. 60 sx cement total.

Name of Plugging Contractor: TDR Construction, Inc. License #: 32218 99998

Address: 15945 W. 288th Paola, KS 66071

Name of Party Responsible for Plugging Fees: JTC Oil, Inc.

State of Kansas County, Johnson, ss.

Tom Cain (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 910 Louisburg, KS 66053

TERRI S. GRATWICK NOTARY PUBLIC STATE OF KANSAS My Appt. Exp. 10/29/06 My Commission Expires: 10/29/06

KCC BEM 12-9-05 Per Operator Tom Cain

Bem