

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/4/05 (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
none Depth to Top: _____ Bottom: _____ T.D. 6900'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-025-21319-00-00
Lease Name: Moorman A
Well Number: #1
Spot Location (QQQQ): Approx - C - E/2 - E/2
2540' Feet from North / South Section Line
710' Feet from East / West Section Line
Sec. 36 Twp. 32S S. R. 25W East West
County: Clark
Date Well Completed: 11/7/005
Plugging Commenced: 11/9/05
Plugging Completed: 11/9/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil,gas,mud	6749	6900	24	40	none
				8-5/8"	732	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hole circulated full of 9.2 ppg mud. Spot Arbuckle plug thru drillpipe @ 6800' - 50 sx; mud between, 1260'-40 sx; mud in between, 750' - 50 sx; mud between, 300 - 40 sx; 60' - 20 sx; Rathole: 15 sx Mousehole: 10 sx
All cement 60/40 pozmix, 6% gel.

Name of Plugging Contractor: VAL Energy, Inc. License #: 5822

Address: P.O. Box 116, Wichita, KS 67201

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.

Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Casey Coats

(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN to before me this 22nd day of November, 20 05
Michelle D. Henney My Commission Expires: 7/10/09
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 7/10/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 28 2005
KCC WICHITA

Bum