

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Baird Oil Co., Inc.

API NO. 15-163-21,433-00-00

ADDRESS Box 428

COUNTY Rooks

Logan, Kansas, 67646

FIELD Valley View

**CONTACT PERSON: Jim R. Baird

PROD. FORMATION Arbuckle

PHONE (913) 689-7456

LEASE Biery

PURCHASER C.R.A. Inc.

WELL NO. #2

ADDRESS P.O. Box 7305

WELL LOCATION 70'W SE NW SE

Kansas City, MO., 64116

920 Ft. from West Line and

DRILLING Abencrombie Drilling Co.

990 Ft. from North Line of

CONTRACTOR


ADDRESS 801 Union Center

the SE/4 SEC. 19 TWP. 7S RGE 19W

Wichita, Kansas, 67201

WELL PLAT

PLUGGING CONTRACTOR ADDRESS



KCC [checked] KGS [checked] (Office Use)

RECEIVED STATE CORPORATION COMMISSION APR - 6 1982 CONSERVATION DIVISION Wichita, Kansas

TOTAL DEPTH PBTD

SPUD DATE 9-14-81 DATE COMPLETED 9-21-81

ELEV: GR 1986 DF 1992 KB 1994

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 225' DV Tool Used? no

AFFIDAVIT

STATE OF KANSAS, COUNTY OF PHILLIPS SS, I, Jim

R. Baird OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Vice-President (OF) Baird Oil Co., Inc.

OPERATOR OF THE Biery LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. #2 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 22nd DAY OF October, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Jim R. Baird April, 19 82

SUBSCRIBED AND SWORN BEFORE ME THIS DAY OF

MARILYN J. ALLEN NOTARY PUBLIC STATE OF KANSAS MY APPT. EXPIRES 2-9-86 MY COMMISSION EXPIRES:

2-9-86

NOTARY PUBLIC

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

SIDE TWO

WELL LOG

15-163-21433-00-00

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Drill Stem Tests - see attached sheet			<u>Log Tops</u>	
			Anhydrite	1504
			B/Anhy	1539
			Topeka	2946
			Heebner	3148
			Toronto	3172
			Lansing	3188
			B/K.C.	3389
			Arbuckle	3438
		LTD	3453	

RELEASED
SEP 01 1983
FROM CONFIDENTIAL

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ~~reused~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	13 1/4"	8 5/8"	20#	225'	common	175	2% gel; 18% salt; 3/4% CFR2
production	7 7/8"	4 1/2"	9.5#	3442	common	200	A/A

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
	none				

TUBING RECORD		
Size	Setting depth	Pecker set at
2 3/8"	TD	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
none	

Date of first production 10/22/81	Producing method (flowing, pumping, gas lift, etc.) pumping	Gravity 30
RATE OF PRODUCTION PER 24 HOURS	Oil 24 bbls.	Gas 0 MCF
	Water % 0 bbls.	Gas-oil ratio 0 CFPS
Disposition of gas (vented, used on lease or sold) vented	Perforations open hole	