

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22112-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 12-20S-11W
2970 feet from S Section Line, 1320 feet from E Section Line
Lease Name: ISERN Well #: 5
County: BARTON Total Vertical Depth: 3315 feet

Operator License No.: 33315
Op Name: MAR-LOU OIL CO., LLC
Address: PO BOX 218
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3302	0	125 SX CMT
SURF	8.625	227	0	175 SX CMT

74
\$107

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2005 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2005 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:
Sanded bottom up to 3252' - topped off with 5 sxs using a dump bailer.
Shot 5 1/2" casing off at 2200'.
Pulled out 22 joints of 5 1/2" casing - spotted 90 sxs cement with 300# hulls at 1300'.
Pulled casing to 450' - spotted 40 sxs cement with 100# hulls.
Pulled casing to 250' - circulated with 75 sxs cement.
Pulled all casing - cellar was full of cement.
Total 205 sxs 60/40 pozmix - 10% gel and 400# hulls.

Perfs:

Top	Bot	Thru	Comments
3313	3315		

RECEIVED
DEC 13 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: CSG

District: 04

Signed Roger A. Moses
(TECHNICIAN)

INVOICED

DATE 12-13-05
INV. NO 2006060856

DEC 07 2005

GABLE OIL COMPANY

P.O. BOX 166

#5 ISERN

12-20-11W
C S/2 S/2 NE

CHASE, KS 67524

CONTR ALLEN DRILLING CO

CTY BARTON

GEOL WAYNE LEBSACK

FIELD CHASE-SILICA

E 1749 KB CM 12/15/80 ^{CARD}ISSUED 3/12/81 IP P 4 BO & 60 BWPD

1744 GL 15-009-22,112 ARB OH 3302 1/2-05

API

SMP	TOPS	DEPTH	DATUM
ARB		3304	-1555
RTD		3305	-1556

8-5/8" 227; 5 1/2" 3302 1/2

NO DST'S

MICT - CO, (ARB OH) NAT, SWB 8 BO &
60 BWPD, POP, P 8 BO & 60 BWPD DECL
TO 4 BO & 60 BWPD IN 30 DAYS

+	+	+
+	+	+
+	+	+

NOTE: ORIGINAL LOC WAS C NE/4

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

13010MI
0749