

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07733-00-00
Spot: NWNENW Sec/Twnshp/Rge: 2-15S-14W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MICHEL F Well #: 1
County: RUSSELL Total Vertical Depth: 3202 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	12	160		
PROD	5.5	425	0	UNKNOWN
SURF	8.625	3190	0	UNKNOWN

104⁰⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2005 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: ZENITH DRILLING CORPORATION Phone: (316) 684-9777

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/11/2005 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

11/07/2005:
Tubing and rods ate off at 415'.
5 1/2" casing set in hole on packer at 425'.
Ran in with overshot several times and brought out pieces of tubing and rods.
11/08/2005:
Overshot got stuck at approximately 410'.
Pulled tubing in two 1 1/2 joints down.
11/09/2005:
Got another overshot. Got hold of tubing. 8 5/8" - 5 1/2" and tubing coming out of hole.
11/10/2005:
Pulled approximately 410' of 8 5/8" 5 1/2" and tubing out of hole.
11/11/2005:
Ran in with tubing. Multiple bridges around 400' - 430'.
Hit hard bridge at 720'.
Circulated with 450 sxs 60/40 pozmix - 10% gel cement.
POOH.
Tied onto 12" casing and pumped 85 sxs cement with 250# hulls.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

RECEIVED
DEC 13 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed CASE MORRIS
(TECHNICIAN)

INVOICED
DATE 12-13-05
INV. NO 2006060858

DEC 08 2005

CORALENA OIL CO #1

F. MICHEL

2-15-14W
NW NE NW

Contr. _____ RUSSELL County

E 1756 Comm 12-30-37 Comp 1-27-38 IP 1367 BOPD

Tops	Depth	Datum
ANHY	760	
TOP	2710	
LANS	2930	
ARB	3190	
TD	3202	

Casing
 12" 160
 8" 3190 *769 2 3/4*
 5 1/2" 425 *Ads. Pump + Tkg at 325*
 SSO 2828-40, 2892-94,
 2950-59
 SO 2965-73
 PAY 3064, PB 3064;
 and Perf
 A/4000; Pmp 64 BO; 3% Wtr
 1st hr, PB

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS