

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20074-00-00
Spot: SESENE Sec/Twnshp/Rge: 34-8S-29W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: MICKEY Well #: 1
County: SHERIDAN Total Vertical Depth: 4525 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4005		
PROD	4.5	4244	0	450 SX CMT
SURF	8.625	222	0	180 SX CMT

#147⁰⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2005 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered 235 sxs Swift Multi-Density Cement - 500# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2005 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 222' w/180 sxs cement.
4 1/2" production casing set at 4244' w/450 sxs cement.
PBTB 4170' with CIBP. TD 4525'.
Casing holes squeezed from 2071'-2102' w/350 sxs.
Perforated 4 1/2" casing at 270' - 1690' - 2445'.
Ran tubing to 2500' - pumped 55 sxs SMD with 300# hulls.
Pulled tubing to 1200' - pumped 50 sxs SMD - cement to surface.
Pulled tubing to surface. Connected to 4 1/2" production casing - pumped 55 sxs SMD.
Max. P.S.I. 400#. S.I.P. 0#.
Cement circulated to surface from perforation in 4 1/2" at 270' and exited from 8 5/8" surface casing.

Perfs:

Top	Bot	Thru	Comments
4096	4099		
4045	4048		
3900	3902		
3822	3826		
3804	3808		

RECEIVED
DEC 13 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #9483.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

1002-

INVOICED
DATE 12-13-06
INV. NO. 2006060851

DEC 08 2005

ROCK ISLAND OIL & REF CO. INC. #1 MICKEY

34-8-29W
SE SE NE

Contr. RED TIGER DRLG

Cty. SHERIDAN

Geol.

Pool HOXIE WEST CONF

E. 2820 KB Cm. 2/5/68 Cp. 3/21/68 IP P 120 BOPD, NW

LANS 4045-99

API 15-179-20,074

LOG Tops	Depth	Datum	Csg. 8" 222/180 SX, 5" 4244
			DST 3588-3600/2', 120' ocsw, 1400' SW, BHP 1030-1017#/30", FP 36-774#
ANHY	2428	+ 390	DST 3768-80/1', 15' socm, BHP 1216-1211#/30" FP 13-27#
HEEB	3877	-1057	DST 3779-85/3', 350' SW, BHP 1256-1225#/30", FP 7--171#
TOR	3900	-1080	DST 3808-36/2', 180' o, 960' SW, BHP 1225-1198 #/30", FP 27-541#
LANS	3916	-1096	DST 3836-56/2', 1900' SW, 5' o, BHP 1216-1207#/30", FP 45-918#
BKC	4159	-1339	DST 3855-70/1', 5' M, BHP 22-27#/30", FP 18-18#
MISS	4488	-1668	DST 3886-3912/90", 230' GIP, 720' GSY o, 120' GSY MO, 360' HOCM, 120' MSW, BHP 1243-1220#/30", FP 31-505#
LTD	4522	-1702	DST 3912-22/75", 10' ocm, BHP 81-68#/30", FP 20-24#
RTD	4525	-1705	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

(CONT'D)

RECORDED
 INDEXED
 17 MAR 1968