

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05046-00-00
Spot: SESWSE Sec/Twnshp/Rge: 28-11S-17W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BEMIS F Well #: 5
County: ELLIS Total Vertical Depth: 3457 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3456	0	UNKNOWN
SURF	8.625	1186	0	UNKNOWN

35
#117

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2005 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TOM BERENS Company: LARIO OIL & GAS COMPANY Phone: (316) 265-5611

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.
Packer left in the hole at 2400'.
TOF at 2386'.
Emergency plug with rig over hole.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2005 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back open hole.
Set CIBP at 3390' and topped with 20' sand.
Packer stuck in the hole at 2400' with SN, 4' sub and 13' tubing. TOF at 2386'.
TIH with tubing to 2350' - mixed and pumped 100 sxs neat cement, followed with 120 sxs cement with 500# hulls.
Cement circulated up 5 1/2".
POOH. Swaged onto 5 1/2" and circulated up 8 5/8" with 80 sxs.
Shut in and pumped to pressure with 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.

Perfs:

RECEIVED
DEC 13 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 12-13-05

NO. 2006060854

Form CP-2/3

DEC 08 2005

SOHIO PETR & LIANO #5 BEMIS 'F'

28-11-17W
SE SW SE

Contr.

ELLIS County

E 1955 Comm 8-13-46 Comp. 8-29-46 IP

854 BOPD

Tops	Depth	Datum
ANH	1175	
SIMP	3450	
ARB	3455	
TD	3457	

Casing
8" 1186
5" 3456

A/500: DF & DD: Swb 95 BOPD
1000' OB: 222 BOPD: A/500

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS