

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24061-00-00
Spot: SWNENE Sec/Twnshp/Rge: 16-16S-13W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: DEUTSCH A Well #: 1
County: BARTON Total Vertical Depth: 3375 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3176		
PROD	5.5	3372	0	150 SX CMT
SURF	8.625	426	0	175 SX CMT

69
\$109

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2005 10:15 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2005 11:15 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto casing and pumped 140 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Squeezed 430'-460' with 135 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3156	3160		
3137	3141		
3060	3065		

RECEIVED
DEC 13 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

MD

Signed Case Morris
(TECHNICIAN)

INVOICED


DATE 12-13-05
INV. NO 2006060.855

DEC 08 2005

~~DATA~~
~~TYPE~~

BHP PETROLEUM (AMERICAS) INC. 16-16-13W
 925 PATTON ROAD DEUTSCH WA SW NE NE
 GREAT BEND, KS. 67530
 CONTR EMPHASIS OIL OPERATIONS CTY BARTON

GEOL BOBBY BEARD FIELD TRAPP



ELV 1923 KB SPD 9/16/85 CARD ISSUED 11/21/85 IP P 134 BO & 18 BWPD
 1918 GL DRLG COMP 9/24/85 ARB OH 3372-3375

LOG	Tops	Depth/Datum	API 15-009-24,061
TOP		3008-1085	8 5/8 " 426 / 175SX, 5 1/2 " 3372 / 150SX
HEEB		3042-1119	DST (1) 3030-84 (SHAW) / 30-60-60-120, NO GTS, REC 30'
TOR		3060-1137	SOCM, SIP 936# & BLDG - 921# & BLDG, FP 84-63 / 93-64#, HP 1692-1632#, BHT 110°
DOUG SH		3074-1151	DST (2) 3127-50 (LANS) / 30-60-60-120, NO GTS, REC 124'
DOUG SD		3088-1165	OCW & M, SIP 397# & BLDG - 405#, FP 76-54 / 100-84#, HP 1728-1710, BHT 113°
BR LM		3124-1201	DST (3) 3340-75 (PENN, ARB) / 30-60-60-120, NO GTS, REC 623' OIL & GSY WTR & M, SIP 1091-1077#, FP 88-94 / 164-225#, HP 1867-1811#, BHT 116°
LANS		3132-1209	MICT - CO, (ARB OH), AC 500G, SWB DWN, GSO, NAT, T&R, POP, P 134 BO & 18 BWPD (GR 37°), 10/3/85
BKC		3350-1427	
ARB		3369-1446	
LTD&RTD		3375-1452	

NOTE: CORRECTION: 11/21/85 - ORIGINALLY FIRST REPORTED AS ENERGY RESERVES GROUP, INC., AS OPERATOR