

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20591-00-00
Spot: NWNENE Sec/Twnshp/Rge: 16-16S-13W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: DEUTSCH Well #: 1-V
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3368	0	175 SX CMT
SURF	8.625	410	0	225 SX CMT

\$109⁵³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2005 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2005 9:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto casing and pumped 275 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Max. P.S.I. 100#. S.I.P. 50#.
Cement in backside - squeezed 433'-464' w/140 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3368	3370		
3256	3261		
3128	3132		

RECEIVED
DEC 13 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 12-13-05

INV. NO 2006060855

DEC 08 2005

CLINTON OIL COMPANY
 WICHITA, KANSAS
 CONTR H-30, INC.

#1-V OTTO DEUTSCH

16-16-13W
 NW NE NE

CTY BARTON

GEOL

FIELD TRAPP

E 1910 KB CM 5/17/71 CARD ISSUED 6/17/71 IP P 51 BOPD N/W NAT.

ARB 3368-70
 GR 38.9

API 15-009-20,591

LOG TOPS DEPTH DATUM 8 5/8" 410/2255x; 5 1/2" 3368/1755x

ANHY	853	+1057	DST(1) 3120-3220(LKC)/90", 60'GIP, 540'
B ANHY	882	+1028	GSY SMO, BHP 743#/45"-939#/65", FP
TOP	2798	- 883	70-314#
HEEB	3034	-1124	DST(2) 3339-68(ARB)/90", 10'CCM, BHP
TOR	3052	-1142	1009#/60"-1026#/90", FP 35-52#
BR LM	3116	-1206	DST(3) 3338-70/1', 165'CGO, 600'SMGO,
LANS	3124	-1214	BHP 1079#/30"-1079#/60", FP 35-
BKC	3341	-1431	348#
ARB	3364	-1454	
LTD	3367 1/2	-1457 1/2	MICT, CO TO 3370 TD SWB 5BOPH NAT., POP
RTD	3370	-1460	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS