

3 022861

15-001-28046-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050053-009
NW,SW,NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.
3395 feet from south section line
5005 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# KENNITH WOLF NO.29
County ALLEN

Name & FEE FUND PLUGGING
Address _____

Well Total Depth 853' feet
Production Pipe: 2 7/8" Size Feet 853"
Surface Casing: 8" Size Feet 25"

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-24,966 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE,LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 12:00P.M. Day: _____ 31 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 853' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS
TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN
None X

Operations Completed: Hour: 2:00P.M. Day: _____ 31 Month: 8 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO
THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1000PSI.
28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
SEP 19 2005
KCC WICHITA

Remarks: (GPS SESSION PT. NO.9) (API NO. 15-001-28,046. FOR WELL NO.29)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

Bm