

3 022955

15-001-28522-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-033
NW,NE,SE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
2488 feet from south section line
903 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101 400

Lease/Well# HAROLD WOLF NO.2-7
County ALLEN

Operator: STATE OF KANSAS FeeFund

Well Total Depth 800' feet

Name & _____

Production Pipe: 2 7/8" Size Feet 800'

Address _____

Surface Casing: 6 5/8" Size Feet 20

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: _____ Day: 11 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY
800' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE
PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF
CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN
None

Operations Completed: Hour: _____ Day: 11 Month: 11 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO
THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 720PSI.
32 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
DEC 09 2005
KCC WICHITA

Remarks: (GPS SESSION PT. NO.39.) (API NO. 15-001-28,522-00-00)
(if additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

Ben