

3 022960

15-001-28176-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-031
NE,NE,SE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
2479 feet from south section line
253 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 10/400-
Operator: STATE OF KANSAS Fee Fund
Name & _____
Address _____
AB oil well Gas Well _____ SWD Well/ Input Well _____

Lease/Well# HAROLD WOLF NO.2-I
County ALLEN
Well Total Depth 800' feet
Production Pipe: 2 7/8" Size Feet 800'
Surface Casing: 6 5/8" Size Feet 20
D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670
Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: _____ Day: 11 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY
800' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE
PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF
CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All _____ Part _____ None

Operations Completed: Hour: _____ Day: 11 Month: 11 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO
THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 545PSI.
31 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
DEC 09 2005
KCC WICHITA

Remarks: (GPS SESSION PT. NO.37.) (API NO. 15-001-28,176-00-00)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

B...