

3 022961

15-001-28523-00-01

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-023
SW,SE,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
2854 feet from south section line
1223 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101 400
Operator: STATE OF KANSAS Fee Fund
Name & _____
Address _____
AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Lease/Well# HAROLD WOLF NO.I-13
County ALLEN
Well Total Depth 817 feet
Production Pipe: 2 7/8" Size Feet 808
Surface Casing: 7" Size Feet 20
E-25,284 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: _____ Day: 11 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 808'. THE PLUGGING PROPOAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____
TECHNICIAN
None _____

Operations Completed: Hour: _____ Day: 11 Month: 11 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE

CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 660PSI.

30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
DEC 09 2005
KCC WICHITA

Remarks: (GPS SESSION PT. NO.31.) (API NO. 15-001-28,523-00-01)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

Bun