

3 022864

10-31-05
KCC
SEM
PerFootages

15-001-28 017-00-01

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER N2 NE,SW,NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.
3808 feet from south section line
4156 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101

Lease/Well# KENNITH WOLF NO.26
County ALLEN

Operator: STATE OF KANSAS FeeFund

Well Total Depth 84.2 feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 842'

Address _____

Surface Casing: 6 1/4" Size Feet 20'

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-24,966 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE,LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: _____ 2 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 842' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS
TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN
None X

Operations Completed: Hour: 10:00P.M. Day: _____ 2 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO
THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750PSI.
28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.15) (API NO.15-001-28,017. FOR WELL NO.26)
(If additional description is necessary, use BACK of this form.)

RECEIVED
SEP 19 2005
KCC WICHITA

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

bn