

3 022860

*KCC
BEM
10-31-05
Per Footages*

15-001-27952-00-01

To:

API NUMBER CONTROL NO. 20050053-008

STATE CORPORATION COMMISSION

W2

NW,SW,NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

3774 feet from south section line

130 S. Market, Room 2078

4980 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# KENNITH WOLF NO.24

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 823 feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 823"

Address _____

Surface Casing: 7" Size Feet 20'

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-24,966 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE,LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: _____ 1 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 823' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS
TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN None X

Operations Completed: Hour: 2:00P.M. Day: _____ 1 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE

CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1200PSI.

35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.8) (API NO. 15-001-27,952. FOR WELL NO.24)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
SEP 19 2005
KCC WICHITA

Bu