

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15.121.01071.00.60  
SWSWNE Sec/Twp/Rge 12-18S-22 E  
3129 feet from south section line  
2506 feet from east section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 101  
Operator: STATE OF KANSAS Fee Fund  
Name & FEE FUND  
Address \_\_\_\_\_  
AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

Lease/Well# NEEDHAM NEE02 #4  
County MIAMI  
Well Total Depth 300 feet  
Production Pipe: 4 1/2 Size Feet 300  
Surface Casing: 6 1/4 Size Feet 20 EST.  
D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_  
Plugging Contractor: K.W. OIL WELL SERVICE Lic. # 3097  
Address: 19450 FORD ROAD CHANUTE, KS. 66720  
Company to plug at: Hour: \_\_\_\_\_ Day: 27 Month: OCT 2005  
Plugging proposal received from: MIKE KEPLEY  
Company Name: KEPLEY WELL SERVICE Phone: 620-431-9212  
Were: PULL PIPE FROM WELL AND FILL WITH CEMENT FROM TD TO SURFACE.

Plugging Proposal Received by: FRANK GUILFOYLE  
TECHNICIAN  
Plugging attended by Agent: All \_\_\_\_\_ Part X None \_\_\_\_\_  
Operations Completed: Hour: \_\_\_\_\_ Day: 28 Month: OCT 2005  
Actual Plugging Report: CLEAR ROAD AND LOCATION TO WELL. PULL 2" AND 1" AND PUMP FROM WELL. MOVE TO RACKS FOR SALVAGE. RUN 1" INSIDE 4.5" TO 275 FT. WASH TO 300 FT. PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE AND TOP OFF WELL. PUT SWEDGE AND VALVE ON 4.5" CASING. SQUEEZE WELL UNTIL IT PRESSURED TO 575 PSI. SHUT IN WELL. PUMP TOTAL OF 35 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL NUMBER: 20050037-002 GPS NO. NEE 02  
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: FRANK GUILFOYLE  
TECHNICIAN

RECEIVED  
NOV 17 2005  
KCC WICHITA