

3 022957

15-207-19626-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-056
NE,SW,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
3338 feet from south section line
1803 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101

Lease/Well# BENNETT B. NO.10
County WOODSON

Operator: STATE OF KANSAS FeeFund

Well Total Depth 750' feet

Name & _____

Production Pipe: _____ Size Feet _____

Address _____

Surface Casing: 12" Size Feet 20'

AB oil well X Gas Well _____ SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE

Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 12:00P.M. Day: _____

Month: 15 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone: 620-432-2300

Were: THIS WAS AN UNCASSED ABNDONED WELL. 20' OF 12" SURFACE CASING
WAS INSTALLED IN THE WELL. THE PLUGGING PROPOSAL WAS TO DRILL OUT THE
WELL TO AS DEEP A DEPTH AS POSSIBLE AND TO CIRCULATE AS MUCH OF THE
WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All 5:00P.M. Part _____
TECHNICIAN
None X

Operations Completed: Hour: _____ Day: _____

Month: 15 Month: 11 2005

Actual Plugging Report: THE WELL WAS DRILLED OUT TO 550'. AT THAT DEPTH
IRON WAS ENCOUNTERED IN THE WELL. 1" PIPE WAS RAN INTO THE WELL TO 550'.
CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE
12" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT
WAS FILLED FROM SURFACE. 160 SACKS OF CEMENT WERE PUMPED INTO THIS
WELL.

RECEIVED
12-09-05
DEC 10 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO.10) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

Bm