

3 022915

15-207-19625-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-009
SE,SW,NE 1/4 Sec/Twp/Rge S28-T.25S.-R.17E.
2810 feet from south section line
1668 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101

Lease/Well# BENNETT B NO. 09
County WOODSON

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 750' feet

Name & _____

Production Pipe: 4 1/2 Size Feet 750'

Address _____

Surface Casing: 7" Size Feet 20'

AB oil well X Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 12 Month: 10 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 750' THAT
HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE
THE 4 1/2" CASING AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF
CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN
None X

Operations Completed: Hour: 10:00A.M. Day: 12 Month: 10 2005

Actual Plugging Report: THE 4 1/2" CASING WAS PERFORATED AT 350'
AND AT 150'. 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 700'. CEMENT WAS
PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT
SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM
SURFACE. 56 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.1) (THIS WAS WELL NO.9 ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN
RECEIVED
NOV 04 2005
KCC WICHITA

B