

3 022943

15-207-19629-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 2000019-039
SW,NE,NE 1/4 Sec/Twp/Rge S.28-T.25S.-R.17E.
4321 feet from south section line
811 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101

Lease/Well# BENNETT "A" NO.12
County WOODSON

Operator: STATE OF KANSAS Fee Fund
Name & _____
Address _____

Well Total Depth 750' feet
Production Pipe: 2" Size Feet 750'
Surface Casing: 8" Size Feet 20'

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W OIL WELL SERVICE, INC Lic. # 3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 12:00P.M. Day: _____ 2 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 750' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. 3/4" PIPE ON A PACKER WAS IN THE WELL. THE PLUGGING PROPOSAL WAS TO REMOVE THE 3/4" PIPE AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All _____ Part _____ None

Operations Completed: Hour: 4:00P.M. Day: _____ 2 Month: 11 2005

Actual Plugging Report: 3/4" PIPE WAS FISHED FROM THE WELL TO 400'.

1" PIPE WAS RAN INTO THE 2" CASING TO 400'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 575'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 239 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.12) (THIS WELL WAS NO.3 ON THE LEASE MAP.)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
NOV 21 2005
KCC WICHITA

Bm