

State Corporation Commission  
 Conservation Division  
 Wichita State Office Bldg.  
 30 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-163-21, 732 0000

LEASE NAME Schoeller

WELL NUMBER #2

2240 Ft. from S Section Line

2240 Ft. from E Section Line

SEC. 19 TWP. 7 RGE. 19 (E) or (W)

COUNTY Look

Date Well Completed 7-10-82

Plugging Commenced 11-25-98

Plugging Completed 11-25-98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bard Oil Co Inc

ADDRESS Box 428 Logan, KS 67646

PHONE# (785) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, O&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 11/18/98 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arb Depth to Top 3440 Bottom - T.D. 3457

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Unconsolidated	sand + shale	Surf	150	8 5/8	220	None
KC	IS + sh	3443 3/8	TD	4 1/2	3441	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Well was perforated at 850'. Mixed 50 sacks of cement and pumped down 8 5/8 casing with 50 # of Halls. Shut-in at 300 psi. Then pumped 450 # of Halls with 150 sacks of cement down the 4 1/2 casing max pressure 500 psi.

Name of Plugging Contractor Allied License No. 5

Address P.O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bard Oil Co. Inc.

STATE OF KS COUNTY OF Phillips, ss.

Jim R. Beard (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Jim R. Beard

(Address) Box 428 Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of December, 19 98

Robert B. Hartman  
 Notary Public

My Commission Expires: 3/29/99  
 USE ONLY ONE SIDE OF EACH FORM

