



15463-00023-00-00

Well Log  
Sinclair Prairie Oil Co

Clarence Hill #1  
Location made 8/2/1944/  
390' fm Nth, 330' fm West lines  
SE/4, 26-7S-18W, Rooks Co., Kas.

Harbor Drig Co - rotary  
Began drig 9/3/1944.  
Comp. drig 9/20/1944.  
T.D. 3560' DRY  
Plugged & Abandoned 9/21/1944

Drillers Log

Rock	40'
Sand	50
Blue Shale	275
Shale & Shells	560
Sand	575
Shale	600
Sand	700
Pyrite	755
Hard Sand	765
Shale	810
Sand	1030
Shale-Red Rock	1130
Red Bed	1350
Anhydrite	1405
Shale	1650
Lime & Shells	1750
Lime	2150
Shale	2170
Lime	2275
Shale-Lime Shells	2395
Lime	2475
Shale & Shells	2660
Shale-Broken Lime	2785
Shale & Lime	2975
Lime	3345
Shale-Lime	3415
Chert-Lime	3425
Cherty Congl.	3530
Lime	3560 TD

292' of 9-5/8" OD 36# SS BR thd  
H40 R2 SH csg set at 267' w/200ax

Top Topoka 2850'  
Top Lan-Kc 3090'  
very small oil show 3175-80'  
Top Congl. 3400'  
Top Arb. 3455' some porosity,  
no show oil or gas.



26 7 18W  
132 28