

STATE OF KANSAS CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-62-3-117

API NUMBER 15-163-21,765-00-00

LEASE NAME Schoeller

WELL NUMBER #3

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 19 TWP. 7 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 8/20/82

Plugging Commenced 5/22/01

Plugging Completed 5/22/01

LEASE OPERATOR Baird Oil Company LLC
 ADDRESS 113 W. Main PO Box 428 Logan, KS. 67646
 PHONE (785) 689-7456 OPERATORS LICENSE NO. 32819

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/8/01 (date)
 by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation KC Depth to Top 3194 Bottom 3398 T.O. 3467

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
unconsolidated sand & shale	surface	170'	8 5/8"	238	None	
KC	shale & limesto	3194	5 1/2"	3448	None	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
Tied onto annulus and mixed 50 sacks of 60/40 Pozmix and 10% Gel and pressured up to 500 psi shut in annulus at 300 psi. Tied onto 5 1/2" production casing and mixed 240 sacks with 100 # of hulls. Maximum pressure 1500 # and shut-in pressure 300 #.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____
Baird Oil Co KCC af

Address PO Box 31 Russell, KS. 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Company LLC

STATE OF Kansas COUNTY OF Phillips, ss.

Jim R. Baird (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) PO Box 428 Logan, KS 67646



before me this 19th day of July 2001

Robert B. Hartman
 Notary Public

My Commission Expires: 3/29/03

OR