

RECEIVED

STATE OF KANSAS
KANSAS CONSERVATION COMMISSION
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-163-22050-00-01

LEASE NAME Biery

WELL NUMBER #4

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 19 TWP. 7 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 5/25/83

Plugging Commenced 5/22/01

Plugging Completed 5/22/01

07-23-2001
CONSERVATION DIVISION

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Baird Oil Company LLC

ADDRESS 113 W Main PO Box 428 Logan, Ks 67646

PHONE# (785) 689-7456 OPERATORS LICENSE NO. 32819

Character of Well Oil FOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/08/01 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached?

Producing Formation KC Depth to Top 3188 Bottom 3391 T.D. 3454

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
unconsolidated	surface	surface	175	8 5/8	208	none
Kansas City	shale & limest.	3188	3391	4 1/2	3445	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Tied into annulus and pressured up to 500 psi Tied into 4 1/2 production casing and mixed 160 sacks of 60/40 Pozmix with 10% Gel with 200 # of hulls. Pressured up to 1000#. Shut-in.

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P.O. Box 31 Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Company LLC

STATE OF KS COUNTY OF Phillips, ss.


Jim R. Baird

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) PO Box 428 Logan, KS. 67646



before me this 19th day of July 2001

Robert B. Hartman
Notary Public

My Commission Expires: 3/29/03

OR