

API NUMBER 163-22,830-00-00

LEASE NAME Rose Culp

WELL NUMBER #3

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

3040 Ft. from S Section Line

2240 Ft. from E Section Line

SEC. 18 TWP. 7 RGE. 19 (E) or (W)

COUNTY LOOKS

Date Well Completed 11/27/85

Plugging Commenced 11/25/98

Plugging Completed 11/25/98

LEASE OPERATOR Baird Oil Co. Inc.

ADDRESS Box 428 Logan, KS 67646

PHONE# (785) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/18/98 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arb Depth to Top 3482 Bottom - T.D. 3492

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand + shale</u>	<u>sand + shale</u>	<u>Surface</u>	<u>150</u>	<u>8 3/8</u>	<u>248</u>	<u>None</u>
<u>kc</u>	<u>shale + limestone</u>	<u>Surface</u>	<u>3436</u>	<u>5 1/2</u>	<u>3485</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Tied on to 8 3/8 and pressured annulus to 500 psi. Then mixed 500# of  
Hulls with 240 lbs of cement 60/40 pozmix w/ 10% gel and pumped  
down 5 1/2 casing. Max press 900 psi Shut-in press 400 psi

Name of Plugging Contractor Allied Tax ID \_\_\_\_\_ License No. 12-11-1998

Address P.O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co. Inc.

STATE OF KS COUNTY OF Phillips, ss.

Jim R. Baird

Above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jim R Baird

(Address) Box 428 Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of December, 19 98

Robert B. Hartman  
 Notary Public

My Commission Expires: 3/29/99  
 USE ONLY ONE SIDE OF EACH FORM

ROBERT B. HARTMAN  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 MY APPT. EXPIRES 3/29/99