

TYPE OR PRINT

NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

15-163-20148-00-00

ROSS HEIRS

WELL NUMBER 2

2310 Ft. from S Section Line

1550 Ft. from E Section Line

SEC. 18 TWP. 7 RGE. 19 (E) or (W)

COUNTY ROOKS

Date Well Completed 10-30-68

Plugging Commenced 7-26-94

Plugging Completed 7-26-94

LEASE OPERATOR Baird Oil Co. Inc

ADDRESS Box 428 Logan KS 67646

PHONE (913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-19-94 (date)

by Dennis Hamel Hays Dist. office (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation ~~KC~~ KC Depth to Top 3220 Bottom 3426 T.D. 3479

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
SND + shale	water	Surface	210	8 5/8	210	None
KC + Arbuckle	oil + wtr	Surface	3473	5 1/2	3473	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Pressured up 8 5/8 to 500#. No cement. Pumped down 5 1/2 casing with 25 sacks cement with 200# of balls followed with 11 sacks Gel and 125 SKS cement. Max pressure 700# Shut-in 500#

Name of Plugging Contractor Allied License No.

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co. Inc.


STATE OF KS COUNTY OF Phillips, ss.

I, Jim R. Baird (Employee of Operator) or (Operator) c

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428 Logan KS 67646



TO before me this 9th day of August, 1994

Robert B. Hartman Notary Public

3/29/95

My Commission Expires:

USE ONLY ONE SIDE OF EACH FORM

RECEIVED STATE CORPORATION COMM. Form CP-4 REVISED 05-88 AUG 15 1994 08-15-1994 CONSERVATION DIVISION WICHITA, KANSAS