

3 022945

15-001-28111-00-01

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-013
SE,NE,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
4528 feet from south section line
235 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# HAROLD WOLF NO.I-1
County ALLEN
Well Total Depth 863' feet
Production Pipe: 2 7/8 Size Feet 834
Surface Casing: 6 1/4 Size Feet 28'

Name & _____
Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-25,284 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 26 Month: 10 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 834' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None _____ X _____

Operations Completed: Hour: 12:00P.M. Day: 26 Month: 10 2005

Actual Plugging Report: 1" PIPE WAS WASHED INTO THE 2 7/8" CASING TO 840'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFCE. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.19) (API NO. 15-001-28,111-00-01)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
NOV 30 2005
KCC WICHITA

Signed: Clayton P. Titel
TECHNICIAN

Bm