

3 022952

*Per Footages  
KCC  
BEM  
12-12-05  
RBB*

15-001-28083-00-00

To: STATE CORPORATION COMMISSION  
API NUMBER \_\_\_\_\_ CONTROL NO. 20050053-038  
NE, NW, NW, SW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION \_\_\_\_\_ 2428 feet from south section line

130 S. Market, Room 2078 \_\_\_\_\_ 4657 feet from east section line  
Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT Lease/Well# MIDDENDORF NO. 03

Operator License # 101 County ALLEN

Operator: STATE OF KANSAS Fee Fund Well Total Depth 850' feet

Name & \_\_\_\_\_ Production Pipe: 2 7/8 Size Feet 850'

Address \_\_\_\_\_ Surface Casing: 6 1/4 Size Feet 20'

AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 10 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 850'

THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING

PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM

SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_  
TECHNICIAN  
None \_\_\_\_\_ X \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 10 Month: 11 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE

CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 950 PSI.

26 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: ( GPS SESSION PT. NO.3 ) ( API NO. 15-001-28,083-00-00 )

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

*Clayton P. Titel*  
TECHNICIAN

RECEIVED  
NOV 30 2005  
KCC WICHITA