

3 022951

15-001-28057-00-01

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050053-037
NW,NW,SW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.
2432 feet from south section line
4973 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# MIDDENDORF NO.1
County ALLEN
Well Total Depth 830' feet
Production Pipe: 2 7/8 Size Feet 850'
Surface Casing: 6 1/4 Size Feet 22'
AB oil well _____ Gas Well _____ SWD Well/ Input Well E-26,011 D & A _____

Name & _____
Address _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: _____ Day: _____ 3 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 826' THAT HAD BEEN
CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO
SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None X

Operations Completed: Hour: _____ Day: _____ 3 Month: 11 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO
THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1000 PSI.
28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.2) (API NO. 15-001-28,057-00-01)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED
NOV 30 2005
KCC WICHITA

Signed: Clayton P. Titel
TECHNICIAN

B...