

3 022948

15001-28191-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-036
NE,NE,SE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
2165 feet from south section line
260 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101

Lease/Well# HAROLD WOLF NO.2-2
County ALLEN

Operator: STATE OF KANSAS Fee Fund
Name &
Address

Well Total Depth 850' feet
Production Pipe: 2 7/8 Size Feet 850'
Surface Casing: 6 1/4 Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: Day: 10 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 850'

THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING
PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM
SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part None X
TECHNICIAN

Operations Completed: Hour: Day: 10 Month: 11 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800PSI.
30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.42) (API NO. 15-001-28,191-00-00)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
NOV 30 2005
KCC WICHITA

Sen