

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-21882-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 22-30S-10E
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BAUDER D (AKA B-3) Well #: 2 (B-3)
County: ELK Total Vertical Depth: 2100 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED
Address: RR1, BOX 1B2
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2100	0	
SURF	7	156	0	

25
\$68

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2005 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: ED TRIBOULET Company: C & E OIL CO. Phone: (620) 647-3610

Proposed
Plugging
Method:

TO USE SAND TO PLUG BACK, THEN PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 09/01/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

USED BAILER TO SAND BACK TO PERFS. RAN 2" TUBING INSIDE 4.5" CASING TO 2095' & PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1140' & PUMPED 5 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" TO 450' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" OUT & TOPPED-OFF WELL. USED TOTAL OF 63 SACKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
2006	2028		

RECEIVED
DEC 09 2005
KCC WICHITA

RECEIVED
KCC DISTRICT #3

OCT 18 2005

RR

CHANUTE, KS

Remarks: PLUGGED ABANDONED OIL WELL.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

INVOICED
DATE 12-12-05
INV. NO. 2006060848