

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20189-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 14-4S-14E
3150 feet from S Section Line, 2130 feet from E Section Line
Lease Name: HOCHARD Well #: 7-14
County: NEMAHA Total Vertical Depth: 2720 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2684		195 SX CMT
SURF	8.625	281		130 SX CMT

40
\$38

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL AND GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2634' TO 2456' CMT FROM 2456' TO 2188' GEL FROM 2188' TO 300' CMT FROM 300' TO SURFACE.

Plugging Proposal Received By: ALAN DUNNING WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2005 3:30 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 2473 feet. Cemented from 2473 feet to 2168 feet. Gelled from 2168 feet to 300 feet. Cemented from 300 feet to surface. A total of 40 sacks of cement were used.

RECEIVED
KCC DISTRICT #3
DEC 1 2005 TCH
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
2404	2406		
2346	2348		
2320	2322		
2291	2293		
2284	2286		
2238	2240		

RECEIVED
DEC 09 2005
KCC WICHITA

Remarks:
Plugged through: DP

District: 03 Signed Taylor C. Herman
(TECHNICIAN)

INVOICED
DATE 12-9-05
INV. NO 2006060.841