

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20176-00-00
Spot: SWSE Sec/Twnshp/Rge: 18-5S-14E
710 feet from S Section Line, 1930 feet from E Section Line
Lease Name: ENGELKE Well #: 15-18
County: NEMAHA Total Vertical Depth: 2679 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2649		190 SX CMT
SURF	8.625	276		147 SX CMT

487⁰⁷

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/22/2005 11:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL AND GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2609' TO 2524' CMT FROM 2524' TO 2296' GEL FROM 2296' TO 300', CMT 300' TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/22/2005 12:30 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

CIBP at 2300 feet. The well was sanded off up to 1630 feet. The well was cemented from 1630 feet to 1410 feet and gelled from 1410 feet to 300 feet. Cement was ran from 300 feet to surface. A total of 70 sacks of cement were used.

Perfs:

Top	Bot	Thru	Comments
2472	2474		
2444	2446		
2417	2419		
2400	2402		
2382	2384		
2351	2353		
2346	2348		

RECEIVED
KCC DISTRICT #3

DEC 1 2005 TCH

CHANUTE, KS

RECEIVED
DEC 09 2005
KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED

DATE

12-9-05

NO. NO.

2006060841