

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-21345-00-00
Spot: NENWSE Sec/Twnshp/Rge: 22-30S-10E
1988 feet from S Section Line, 1848 feet from E Section Line
Lease Name: BAUDER A (AKA M. REID #1) Well #: 3 (REID 1)
County: ELK Total Vertical Depth: 2010 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED
Address: RR1, BOX 1B2
MOLINE, KS 67353

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD | 4.5 | 2010 | 0 | |
| SURF | 7 | 70 | 0 | |

#165 33

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2005 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: ED TRIBOULET Company: C & E OIL CO. Phone: (620) 647-3610

Proposed
Plugging
Method:

TO USE SAND TO PLUG BACK, THEN PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 09/01/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

USED BAILER TO SAND BACK TO PERFS. RAN 2" TUBING INSIDE 4.5" CASING TO 2005' & PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1100' & PUMPED 5 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" TO 450' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" OUT & TOPPED-OFF WELL. USED TOTAL OF 60 SACKS CEMENT.

RECEIVED
KCC DISTRICT #3

OCT 18 2005

CHANUTE, KS

RR

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1976 | 1988 | | |

RECEIVED
DEC 09 2005
KCC WICHITA

Remarks: PLUGGED ABANDONED WELL.

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

INVOICED

DATE 12.12-05

INV. NO 2006060848