

8-14

294  
R

6 070939

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,177-00-00

SW NE SW, SEC. 19, T 7 S, R 19 (W) E

1650 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Collins Well # 4

Operator: Baird Oil Co., Inc.

County Rooks 113.91

Name & Address P.O. Box 428

Well Total Depth 3505 feet

Logan, Kansas 67646

Conductor Pipe: Size feet

Jim Baird

Surface Casing: Size 8 5/8 feet 215'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number

Address 801 Union Center, Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 14 Month: August Year: 19 91

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 913-689-7456

were: 8 5/8" 215' S.P. cwc. w/165 sx. 60/40 Poz. - 2% Gel. - 3% C.C. By Allied Cement.

Arbuckle @ 3460'. Elv. 2000'. Anhy. 1525'. Mud condition 46 vis. 9.4 Wt. 8.8 W.L.

No circulation problems. Proposal circulate hole. Order 215 sx. 60/40 Pozmix -

6% Gel. - 3% C.C. - 1 sk. Flocele. Spot with drill stem. Heavy mud between all

plugs. 25 sx. @ 3400' - 25 sx. @ 1535' - 100 sx. w/1 sk. F.C. @ 900' - 40 sx. @ 260' -

10 sx. @ 40'. 15 sx. in Plugging Proposal Received by Marion J. Schmidt  
Rathole (circulate) (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30A.M. Day: 14th Month: August Year: 19 91

ACTUAL PLUGGING REPORT Barid Oil ordered 215 sx. 60/40 Pozmix - 6% Gel. - 3% C.C. and

1 sx. Flocele. Circulated hole. Spotted with drill stem. Heavy mud between all plugs.

1st. plug @ 3400' w/25 sx. cement. 4th plug @ 260' w/40 sx. cement.

2nd plug @ 1535' w/25 sx. cement. 5th plug @ 40' w/10 sx. cement

3rd plug @ 900' w/100 sx. cement w/1 sx. Flocele.

15 sx. in Rathole (Circulate)

Remarks: Cemented By: Allied Cement.

RECEIVED  
STATE CORPORATION COMMISSION

INVOICED (Additional description is necessary, use BACK of this form.) AUG 29 1991

I (XXXXXX did not) observe this plugging.

DATE 9-11-91

INV. NO. 33061

Signed Marion J. Schmidt  
CONSERVATION DIVISION  
WICHITA, KANSAS  
(TECHNICIAN)