

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22050-00-01
Spot: CNENWSE Sec/Twnshp/Rge: 19-7S-19W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BIERY Well Number: 4
County: ROOKS Total Vertical Depth: 3445 feet

Operator License No.: 5352
Op Name: BAIRD OIL CO, INC
Address: BOX 428 MAIN STREET
LOGAN, KS 67646

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 208
Production: Size 4.5 feet: 3445
Liner: Size _____ feet:

\$111.96

Well Type: EOR UIC Docket No: E23926.1 Date/Time to Plug: 05/22/2001 8:00 AM
Plug Co. License No.: 32819 Plug Co. Name: BAIRD OIL COMPANY LLC
Proposal Rcvd. from: JIM BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Order 160 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/22/2001 10:30 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 208' w/200 sxs cwc. 4 1/2" set at 3445' w/650 sxs cwc.
Perf at 1510' - Two staged.
Prod Perfs 3318' - 3386'.
Squeezed 4 1/2" with 160 sxs cement blend with 200# hulls mixed in to Max. P.S.I. 1000#. Held.
Plug complete.
Test 8 5/8" to 500# P.S.I. Cement at surface.

INVOICED
DATE 6-14-01
INV. NO. 2001061946

RECEIVED
KANSAS CORPORATION COMMISSION
06-13-2001
JUN 13 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

MD

Signed Carl Goodrow
(TECHNICIAN)

JUN 06 2001

BAIRD OIL COMPANY
BOX 7

REPLACEMENT CARD

19-7-19W
NE NW SE


LOGAN, KS 67646

#4 BIERY

CONTR ABERCROMBIE DRILLING, INC. CTY ROOKS

GEOL _____

FIELD VALLEY VIEW



ELV 1993 KB SPD 5/21/83 CARD ISSUED 7/14/83 IP P 12.33 BO & 74

1988 GL

BWPD

API 15-163-22,050

LKC 3318-3386 OA

| LOG | Tops | Depth/Datum |
|-------|------------|-------------|
| ANH | | 1506+ 487 |
| B/ANH | | 1534+ 459 |
| TOP | | 2946- 953 |
| HEE3 | | 3148-1155 |
| TOR | | 3172-1179 |
| LANS | | 3188-1195 |
| SHALE | | 3306-1313 |
| BKC | | 3391-1398 |
| ARB | | 3442-1449 |
| RTD | | 3453-1460 |
| LTD | | 3454-1461 |

8 5/8 " 208/200SX, 4 1/2 " 3445/250SX
DST (1) 3432-53 (PENN, ARB) / 45-60-45-60, REC 15' CL OIL,
45' HOCM, SIP 224-173#, FP 30-30 / 40-40#
MCT - CO, PF (LKC) 3378-86, W/ 4 SPF, AC 500G (28%) &
2000G (15%) & 6 BBLS OVERFLUSH, SWB DWN, SO, PF (LKC)
3356-64, W/ 4 SPF, AC 500G (28%) & 2000G (15%) & 6 BBLS
OVERFLUSH, SWB DWN, SO, PF (LKC) 3340-44, W/ 4 SPF, AC
500G (28%) & 1500G (15%) & 6 BBLS OVERFLUSH, SWB DWN,
SO, PF (LKC) 3324-30, 3318-24, W/ 4 SPF, AC 2500G (15%) & 6
BBLS OVERFLUSH, SWB DWN, SO, POP, P-89 BFPH (66% W/
1ST WK, 58.79 BFPD (75% W)/ 2ND WK, 48.16 BFPD (74.4% W/
3RD WK (GR 30°)

INFO RELEASED: 10/25/84 - WAS OIL WELL - TIGHT HOLE
NOTE: INFO RELEASED 9/15/83 - ADDED ELEV & PROD FORMATION

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS