

4-031957

7-26

TQ:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,731-00-00
20'E.of
NW SW SE /4 SEC. 19 , 07 S, 19 W
990 feet from S section line
2240 feet from E section line

Operator license# 5352

Lease Biery well # 3

Operator: Baird Oil Company, Inc.

County Rooks

Address: Box 428
Logan, Kansas 67646

Well total depth 3438 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1392 feet

111.73

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 26 Month: July Year: 94

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 26, Month: July, Year: 94

Actual plugging report: 8 5/8" set @ 1392' w/500 sxs. cwc. 4 1/2" set at 3424' w/235 sxs. Prod. perfs. 3299' - 3366'. Squeezed 4 1/2" w/25 sxs. cement blend w/200# hulls followed with 8 sxs. gel, followed by 125 sxs. cement blend to Max. P.S.I. 600#. Close in P.S.I. 300#. Squeezed 8 5/8" annulus w/100 sxs. cement blend w/100# hulls mixed into Max. P.S.I. 500#. Close in P.S.I. 300#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did not observe the plugging.

INVOICED

AUG 15 1994

DATE

INV. NO. 40934

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED
KANSAS CORPORATION COM
08-05-1994
AUG 05 1994
CONSERVATION DIVISION
WICHITA, KS