

4-060411

7-4

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,229 ⁰⁰⁻⁰⁰
50'E. of
E2 SE SW /4 SEC. 24, 07 S, 19 W
660 feet from S section line
3020 feet from E section line

Operator license# 3456 Lease Axelson well # 8-24

Operator: A.F.G. Energy, Inc. County Rooks

Address: P.O. Box 458 Well total depth 3465 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 320 feet

112.61

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Duke Drilling Company, Inc. License# 5929

Address: 310 W. Central #117 - Wichita, Kansas 67202

Company to plug at: Hour: 11:30A.M Day: 4 Month: July Year: 93

Plugging proposal received from: Rich Wheeler

Company: Duke Drilling Company, Inc. Phone: 316-267-1331

Were: Order 215 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per. sx.
Space all plug with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:30P.M., Day: 4, Month: July, Year: 93

Actual plugging report:
1st. plug at 3418' w/25 sxs. - Arbuckle top at 3428'.
2nd. plug at 1400' w/25 sxs. - Anhydrite 1388' - 1422'.
3rd. plug at 805' w/100 sxs. - Dakota 503' - 803'.
4th. plug at 370' w/40 sxs. - Surface pipe to 320'.
5th. plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1903 GL

I did did not observe the plugging.

7-14-93

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1993

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
DH (agent)

Form CP-2/3

INVOICED

DATE 7-23-93

INV. NO. 38195