

6030421

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22,657-00-02  
SW, SEC. 29 T. 7 S., R. 19 W.  
350 feet from (S) section line  
4370 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name Stice Well # 1

Operator Name & Address

County Roos 111.15

Energy Exploration Inc.  
120 S. Market Ste 606  
Wichita, Kansas 67202

Well Total Depth 3420 feet

Conductor Pipe: Size 13 3/8 feet 68'

Surface Casing: Size 8 5/8 feet 1446

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Albercrombie Drilg License Number 182

Address 801 Union Center Wichita Kansas 67202

Company to plug at: Hour: AM Day: 20 Month: 4 Year: 19 85

Plugging proposal received from Bill Craig

(company name) albercrombie Drilg (phone) \_\_\_\_\_

were: Conductor 13 3/8" set @ 68' w/ 130# 8 5/8" set @ 1446' w/ 600# w/ no loss of fluid and no less than 36 vis. mud in hole spot cement plugs with 4 1/2" O.P. Order 150 #p. 50/50 #p. 6% gel. 3% cc. Sun Cement RECEIVED 8 5/8" w.p.

STATE CORPORATION COMMISSION 4-20-85

APR 20 1985

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

CONSERVATION DIVISION  
Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 7:30AM Day: 20 Month: 4 Year: 19 85

ACTUAL PLUGGING REPORT spot O.P. @ 3375 displace 25 #p Cement mix.

Laydown D.P. to 1445 displace 50 #p Cement mix Laydown D.P. to 750 displace 50 #p Cement mix. Laydown D.P. Push w.p. to Kelly depth fill hole with cement mix to bottom of Celler 10 #p. Cement mix. Displace 15 #p Cement mix in Rathole with joint of pipe. Plug Complete.

Remarks: Elev. 1921 KB only 1478-1514 arb. 3376  
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did/did not) observe this plugging.

DATE 5-7-85

Signed Carl Goodrow (TECHNICIAN)

16  
4-26-85  
MPT

INV NO. 7964