

4-042025

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-21,449-0000

NW SW SW \_\_\_\_\_ /4 SEC. 28, 07 S, 19 W  
990 feet from S section line  
4950 feet from E Section line

10-07

Operator license# 4116

Lease: Lorbeer Well # 1

Operator: Stice Oil Company

County: Rooks 109-14

Address: 709 N. Elm  
Stockton, Kansas 67669

Well total depth 3358 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 329 Feet  
W/N/A sxs.cmt.

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Mike's Testing & Salvage License# \_\_\_\_\_

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 9:00 A.M. Day: 6 Month: October Year 1999

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage Phone: \_\_\_\_\_

Were: Ordered 200 sxs 60/40 pozmix - 10% gel and 500# hulls.  
4 1/2" casing set at 3352' w/150 sxs cement. Perfs at 3152' - 3288'.

RECEIVED  
KANSAS CORP COM  
OCT 27 12:35

10-27-99

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:15 P.M., Day 7, Month: October, Year: 1999

Actual plugging report: Plug bottom: Sanded to 3100' with 5 sxs cement on sand. Took casing stretch (3"-4"). Perf casing at 1450' and 850'. RU Cementers to casing and squeezed casing with 100 sxs cement and 300# hulls. Displaced to 400'. Shot casing at 400' - pulled sub. RU Cementers to 4 1/2" casing - spotted 100 sxs cement with 200# hulls. Cement circulated at surface. Pulled 400' casing with 4-5 bbls of cement circulated in cellar. Check cement top 10-19-99 - 18" to 20" cement cap in cellar.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD \_\_\_ BAD \_\_\_ Anhy.plug: YES \_\_\_ X \_\_\_ NO \_\_\_  
Bottom plug(in place): YES \_\_\_ , CALC \_\_\_ , NO \_\_\_ Dakota plug: YES \_\_\_ X \_\_\_ , NO \_\_\_  
Plugged through TUBING \_\_\_ CASING \_\_\_\_\_. Elevation: \_\_\_\_\_ G.L. \_\_\_\_\_

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED  
DATE 10-29  
TEL. NO. 60787

(2)