

6 020249

15-065-22214-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SE-NW-SE, SEC. 1, T. 7 S, R 21 W/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-22214

1650 N feet from S section line  
1650 W feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5783

Lease Name Trexler Well # 1

Operator: Galloway Drlg. Co Inc.  
Name & Address 340 Broadway Plaza  
Wichita Ks. 67202.

County Graham. 119.60

Well Total Depth 3680 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Galloway Drlg. Co Inc. License Number 5783

Address 340 Broadway Plaza 105 S. Broadway, Wichita Ks

Company to plug at: Hour: PM, Day: 31 Month: July Year: 19 85

Plugging proposal received from Carl McGuire

(company name) Galloway Drlg. Co Inc. (phone) 316-263-1793

were: Cir Heavy Mud. 20 min + Pump down drillstem. 6 1/4 Poz  
4 1/2 Gel. 3% cc. w/ 1' sx Flo Cel. 20 sx @ 3570, 20 sx @ 1770  
100 sx @ 980, 40 sx @ 250, 10. sx 40' on Solid Bridge 10 sx R.H.

Plugging Proposal Received by Jillbut Balthazar  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:00AM Day: 31 Month: July Year: 19 85

ACTUAL PLUGGING REPORT Cir Heavy Mud. + Pumped down drillstem  
6 1/4 Poz 4 1/2 Gel. 3% cc w/ 1' sx Flo Cel. 20. sx @ 3570. 20 sx  
@ 1770, 100 sx @ 980; 40 sx @ 250. 10. sx on Solid Bridge @ 40'  
10. sx in Rat Hole.

Remarks: Cemented By Allied.

(Additional description is necessary, use BACK of this form.)

I (did / did not) conserve this plugging.

DATE 9507

INV. NO. 9507

7-31

Signed Jillbut Balthazar  
(TECHNICIAN)

RECEIVED  
CORPORATION DIVISION

AUG 9 1985

CONSERVATION DIVISION  
Wichita, Kansas

8-8-85  
MPS