



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-163-20301-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 23 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
04-23-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Howard of Sage Drlg. has this

date requested permission to plug the following described well:

Mr. Howard guarantees payment of the plugging fee.

Operator's full Name: American Drlg. Corp.

Complete Address: 360 Sutton Place Wichita, Kansas

Lease Name: Western Auto Well No. 1

Location: NE SW SW Sec. 7 Twp. 7 Rge. (E)(W) 20

County: Rooks Total Depth 3627 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Howard was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace

70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Maddy  
Conservation Division Agent