



15-163-20506-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

NOV 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

11-5-73

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Niernberger of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corporation

Complete Address: 200 W. Douglas Wichita, Ks.

Lease Name: Schneider Well No. 1

Location: SE NE NW Sec. 28 Twp. 7 Rge. (E)(W) 19

County: Rooks Total Depth 3385' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Niernberger was instructed to plug the well as follows:  
Gum pits, circulate heavy mud, set cementing plug at 650' and displace  
70 sk cmt thru drill pipe. Heavy mud to 215' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent