

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 20,872 - 00000 (of this well)

Operator's Full Name Mai Operations

Complete Address Box 33, Russell, Kansas

Lease Name LeSage Well No. 1

Location NW SW NW Sec. 17 Twp. 7 Rge. (E) (W) 20

County Rooks Total Depth 3396'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Torando Drlg.

Address        License No.       

Operation Completed: Hour 6 P. Day 10 Month 12 Year 1978

The above well was plugged as follows:

RTD 3396' 8 5/8 csg set 202' cwc 150 sk. Plg Mat 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.  
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1978  
12-12-78

I hereby certify that the above well was plugged as herein stated.

**INVOICED** CONSERVATION DIVISION  
Wichita, Kansas

Signed: Ben Messer  
Well Plugging Supervisor

DATE 12-13-78  
INV. NO. 8735-W