

15-163-01110-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 73-25

LOCATION NE NE NE

SEC. 19 TWP. 7 RGE. 19

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Schoeller

Operator W. J. Coppinger Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3486 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement - 5 1/2" at 3476' with  
50 sax cement behind.

Run 5 sax cement on bottom, set rock bridge and run 5 sax cement  
with dump bailer, pulled 5 1/2", filled hole with heavy mud to  
180', set rock bridge and 15 sax cement, filled with mud to  
40', set rock bridge and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
04-24-1951  
APR 24 1951

CONSERVATION DIVISION  
Wichita, Kansas  
*[Signature]*  
District Conservation Agent

Date 4-20-51

**PLUGGING**  
FILE SEC 19 7 R-19  
BOOK PAGE 73 25